

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21296-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 10-25S-9W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ETHEL Well #: 1
County: RENO Total Vertical Depth: 4035 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 4033 150 SX
SURF Size: 8.625 feet: 180 200 SX

14
\$ 131

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2005 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand perforations to 3815' and put 5 sacks of cement on top. Cut off casing. Pull to 1400' and pump 35 sacks of cement. Pull to 800' and pump 35 sacks of cement. Pull casing to 250' and circulate cement to surface.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/04/2005 4:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3815' and put 5 sacks of cement on top. Cut off casing at 2629'. Pulled to 1400' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled to 800' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 250' and circulated cement to surface.

Allied Cement #20063

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3868	3878		
RECEIVED KCC DISTRICT #2 APR - 6 2005 WICHITA, KS			

RECEIVED
APR 11 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICE
DATE 4-12-05
WEL. NO. 2005061397