

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-01030-00-00
Spot: NWNE Sec/Twnshp/Rge: 29-17S-10W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: JANSSEN D Well #: 1
County: ELLSWORTH Total Vertical Depth: 3304 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3293 100 SX
SURF Size: 8.625 feet: 221 200 SX

#107³⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2005 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Sand 50' above open hole. Put 5 sacks cement on top and perforate at 1300', 1000', and 270'. Run tubing to 1300' and pump
Plugging 35 sacks of cement. Pull tubing to 1000' and pump 35 sacks of cement. Pull tubing to 270' and circulate cement to surface.
Method:

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/18/2005 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded 50' open hole to 3240'. Put 5 sacks cement on top and perforated at 1300', 1000', and 270'. Run tubing to 1300' and pumped 35 sacks of cement with 50 lbs of cotton hulls. Pulled tubing to 1000' and pumped 35 sacks of cement with 50 lbs cotton hulls. Pulled tubing to 270' and circulated cement to surface.

Allied Cement #20655

60/40 posmix with 4% gel

RECEIVED
APR 11 2005
KCC WICHITA

RECEIVED
KCC DISTRICT #2
MAR 31 2005
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICE

DATE 4-12-05

2005061397