

6 031462

12-11

303

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,074-00-00
NE SE NW, SEC. 22, T 6 S, R 23 W/E^{XX}

TECHNICIAN'S PLUGGING REPORT

Operator License # 6861

Operator: Ron's Oil Operations Inc.
Name & Address: Route 1 Box 194
Penokee, Ks. 67659

3630 feet from S section line
2970 feet from E section line
Lease Name Morris Well # 1
County Graham 125.12
Well Total Depth 3850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size _____ feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Co. License Number _____

Address Russell, KS.

Company to plug at: Hour: _____ AM Day: 11 Month: Dec. Year: 19 90

Plugging proposal received from Ron Nickelson
(company name) Ron's Oil Oper (phone) _____

were: 8 5/8 263 w/200 sks. 4 1/2 set at 3837 w/300 sks. PBD 3850.

Perf 3601 - 3755. 4 1/2 cemented from anhy to surf.

Order 300 sks 65/35 poz 10% gel 500 lbs. hulls. allied Cement Co.

M and L Water Trucks.

Hole open to perfs.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 11 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT Sq 4 1/2 w/275 sks cement blend w/500 lbs. hulls.

mixed in to max psi 1000 lbs. Close in psi 1000 lbs.

Sq 8 5/8 to 600 lbs. psi w/no fluid cement at surf.

Plug complete.

Stamp: STATE CORPORATION COMMISSION
JAN 4 1991
1-4-91

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-7-91

INV. NO. 30583

12-11

J.R.S.

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow