

4-27

4-060388

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,706 00-00

NE NE SE /4 SEC. 21, 06 S, 23 W
2310 feet from S section line
330 feet from E section line

Operator license# 4767 Lease Schaben 21-D well # 1

Operator: Ritchie Exploration, Inc. County Graham

Address: 125 N. Market Well total depth 3835 feet
Suite 1000 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 246 feet

124.63

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67201

Company to plug at: Hour: 9:00P.M. Day: 27 Month: April Year: 93

Plugging proposal received from: Lloyd Delleette

Company: Murfin Drilling Company Phone:

Were: Order 190 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per. sx.
Space all plugs with heavy drilling mud through drill pipe.
No arbuckle.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:00P.M., Day: 27, Month: April, Year: 93

Actual plugging report:
1st. plug at 2080' w/ 25 sxs. - Anhydrite 2060' - 2091'.
2nd. plug at 1225' w/100 sxs. - Dakota 925' - 1225'.
3rd. plug at 300' w/ 40 sxs. - Surface pipe to 246'.
4th. plug at 40' w/ 10 sxs.
Rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1993

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2375 GL

5-12-93

I did not [X] observe the plugging.

JA (agent)
Form CP-2/3

INVOICED
DATE 5-14-93
INV. NO. 37694