

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-30372-00-00
Spot: NWNE Sec/Twnshp/Rge: 27-21S-7W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: STEIERL Well #: 2
County: RICE Total Vertical Depth: 3475 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 4.5 feet: 3474 100 SX CMT
SURF Size: 8.625 feet: 208 SURFACE

\$ 112⁹⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2005 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/18/2005 5:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Shot off stuck tubing in casing at 1180'. Pumped 50 sacks of cement through casing after pulling tubing. Pulled casing apart at 2556'. Pulled 1000' and pumped 35 sacks of cement. Pulled casing to 550' and pumped 35 sacks of cement. Pulled to 270' and circulated cement to surface.

Copeland Cement #24932

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3407	3415		
RECEIVED KCC DISTRICT #2 MAR 31 2005 WICHITA, KS			

RECEIVED
APR 11 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
4-12-05
2005061395