

KANSAS

Form CP-3
Rev. 6-9-67

10 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JAN 2 1968
1-2-68

15-065-20116-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name E. K. Edmiston,

Complete Address 425 First National Bank Building, Wichita, Kansas.

Lease Name Conoco-Bangle Well No. 1

Location SW-SE-NW Sec. 8 Twp. 6 Rge. (E) (W) 25

County Graham Total Depth 3795'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 6:00 PM Day 31 Month 12 Year 1967

The above well was plugged as follows:

211'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota section from 1075' to 1250'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Pichala*
Well Plugging Supervisor

DATE 1-3-68
INV. NO. 7024-W