

KANSAS

14
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT
15-065-20037-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1967
5-8-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Company,
Complete Address: 1130 Wichita Plaza, Wichita, Kansas.
Lease Name Ward Well No. 2
Location NW-NE-SW Sec. 31 Twp. 6 Rge. (E) (W) 25
County Graham Total Depth 2407 (Anhydrite well)
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Leben Drilling, Incorporated,
Address: Box #486, Great Bend, Kansas. License No.
Operation Completed: Hour 1:15PM Day 1 Month 5 Year 1967

The Above well was plugged as follows:

299'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Lost circulation was encountered on top of Anhydrite. Cemented loss six times, still unable to regain circulation. Drilled hole dry to base of Anhydrite and logged well, decision was made to abandon. Checked fluid level in well found @ 350', set bridge on top of fluid with 1 sack hulls and plug with 25 Sx. cement. Filled hole with mud to 295' set plug with 1/2 sk. hulls and 10 Sx. cement. Filled hole with heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 5/11/67
INV. NO. 5183-W