

Form CP-3
Rev. 6-26-62

¹⁰
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

15-065-19038-00-00

FEB 17 1964
2-17-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John O. Farmer, Incorporated,
Complete Address: 370 West Wichita, Russell, Kansas.
Lease Name Ward Well No. 1
Location NE-SW-SE Sec. 31 Twp. 6 Rge. (E) (W) 25
County Graham Total Depth 3895
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Above
Address: License No.
Operation Completed: Hour 9:30PM Day 11 Month 2 Year 1964

The Above well was plugged as follows:

265'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx. cement
thru DP. Heavy mud to 250', set plug with 1/4 sack hulls and displaced 20 Sx.
cement thru DP. @ 250'. Heavy mud to 40', set plug with 1/2 sack hulls and
10 Sx. cement to bottom of cellar.

INVOICED
I hereby certify that the above well was plugged as herein stated.

DATE 2/18/64
INV. NO. 8660-4

Signed: N. D. Nichols
Well Plugging Supervisor