

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20114-00-00

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1967
12-21-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Schoen Well No. 1

Location CNE-SE Sec. 1 Twp. 6 Rge. (E) (W) 25

County Graham Total Depth 4082

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 3:00 PM Day 19 Month 12 Year 1967

The above well was plugged as follows:

185'--8 5/8" Surface pipe, cement circulated with 170 Sx.
Dakota section from 775' to 980'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru
DP from 1000' to 680'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from
180' to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/22/67
INV. NO. 6964-W

Signed: A. L. Nichols
Well Plugging Supervisor