

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20399-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1970
CONSERVATION DIVISION
Wichita, Kansas
12-16-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Magness Petroleum Company,

Complete Address 300 National Foundation Life Bldg., Oklahoma City, Oklahoma.

Lease Name Jeffrey Well No. 1

Location NE-NE-SW Sec. 32 Twp. 6 Rge. (E) (W) 25

County Graham Total Depth 3890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 5:30 AM Day 11 Month 12 Year 1970

The above well was plugged as follows:

310'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/17/70
INV. NO. 3085-u