

KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20305-00-0 Δ

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
2-19-70

Operator's Full Name L. J. Dreiling & Sons, Incorporated.

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Hickert Well No. 1

Location SW-SW-SW Sec. 27 Twp. 6 Rge. (E) (W) 25

County Graham Total Depth 4254'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 6:00 PM Day 17 Month 2 Year 1970

The above well was plugged as follows:

324'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru  
DP from 1300' to 975'. Pulled DP to 335' and displaced 25 Sx. cement thru DP from  
335' to 260'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 2/19/70  
INV. NO. 1465-W