

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

15-065-00815-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

APR 14 1975

4-14-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Glenn W. Peel Oil Operator

Complete Address RR #3, Box 144B, Wichita Kansas, 67226

Lease Name Lindeman Well No. # 1

Location SE-SE-SE Sec. 31 Twp. 6 Rge. 25 (E) (W) X

County Graham Total Depth 3845

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Co, Inc.

Address P.O. Box 364, Great Bend, Ks. License No. 399

Operation Completed: Hour 4:00 PM Day 9 Month April Year 1975

The above well was plugged as follows:

KB. 2562' Daktop 1500' SP 285' of 8 5/8" cwc.  
5 1/2" casing set @ 3841' w/125 sx Plug Back 3794'  
Perf. 3699 to 3707 Bottom Plug @ 3675' w/25' of sand + 5 sx cem.  
Pumped down 8 5/8" SP, 5 sx Hulls, 12 sx Gel, 70 sx cem. 50/50  
Pozmix 6% Gel, 18 sx Gel, Release Plug + 55 sx cement  
50/50 Pozmix 6% Gel on Top. Max pres. 150 lbs.  
Recovered 1300' of 8 5/8" casing.  
Cemented by Halliburton -

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Gilbert Balthasar  
Well Plugging Supervisor

DATE 4/15/75  
INV. NO. 1150-W