

DISTRICT CONSERVATION AGENT'S REPORT

15-065-00 893-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 35-33

LOCATION NW SE NW

SEC. 30 TWP. 6 RGE. 25

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 2 Lease Tedro

Operator Jones, Shelburne^d Farmer^d Inc. Address Russell, Kans

Field _____ County Graham

Total Depth 3885 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 320' circulated with cement - 5 1/2" at 3885' with 100
sax cement behind - perforated at 3720.

Filled with sand to 3700', set cementing plug at 4 sax cement,
pulled 1000' 5 1/2" - filled with mud to 320', set rock and 15 sax
cement, mud to 40', set rock and 10 sax cement to bottom cellar,

E. J. [Signature]
District Conservation Agent

3-8-56

Date _____

PLUGGING
FILE NO. 30 6 25W
35 33
BOOK _____ LINE _____

3-15-56