

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation

Address: 1201 Lake Robbins Dr., The Woodlands, TX 77380

Phone: (832) 636-3128 Operator License # 4549

Type of Well: SWD Docket # _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Mike Heffern (KCC District Agent's)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle Depth to Top: 2886 Bottom: 3082 T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number 15- 111-20426-00-00

Lease Name Ahlstrom Trust

Well Number 1-14

Spot Location (QQQQ) _____ CNE

1320 Feet from North / South Line of Section

1320 Feet from East / West Line of Section

Sec. 14 Twp. 16 S. R. 12 East West

County: Lyon

Date Well Completed: 10/25/03

Plugging Commenced: 8/5/04

Plugging Completed: 8/10/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled out
	Surface casing	0	244	9-5/8"	244'	0-4'
Arbuckle	Production casing	0	2886	7"	2886'	850'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Set CIBP @ 2800' and dumped 2 sxs of cement on top. Cut 7" casing at 850'. Pumped cement plug @ 100' with 20 sxs cement to surface. Place heavy mud between plugs. Cut surface casing @ 4' and capped.

Name of Plugging Contractor: Eagle Well Services License # 7407

Address P. O. Box 1597, Liberal, KS 67901

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Jerry N. Blossom (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Jerry N. Blossom

(Address) 1201 Lake Robbins Dr., The Woodlands, TX 77380

SUBSCRIBED and SWORN TO before me this 12 day of April, 20 05

claudsgardner My Commission Expires: 10 Aug. 2006
Notary Public

CONSERVATION DIVISION
WICHITA, KS

APR 13 2005

