

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Imperial American Oil Corporation

Address: 900 N Tyler Road #14, Wichita KS 67212

Phone: (316) 721-0036 Operator License #: 32511 exp 9/30/2004

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: November 27, 2003 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

see ser 4/13/05 RBMS

Depth to Top: Bottom: T.D. 3800

API Number: 15-051-25072-00-00

Lease Name: Rosemary

Well Number: 17-1X1305

Spot Location (QQQQ): W/2 - W/2 - SW/4 - 1305

Feet from North South Section Line East West Section Line

Sec. 17 Twp. 11 S. R. 20 East West

County: Ellis

Date Well Completed: 1/3/01

Plugging Commenced: 10/27/03

Plugging Completed: 10/27/03

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Ran Tubing, Circulated w/120 sx and 300# hulls. Pulled tubing. Squeezed 5-1/2" w/10 sx cement. Pressure to 900 psi. SIP 500 psi Annulus full.

RECEIVED

Name of Plugging Contractor: Allied Cementing Company Murfin Drilling License #: NA 30606 APR 12 2005

Address: PO Box 31, Russell KS 67665

KCC WICHITA


Name of Party Responsible for Plugging Fees: Operator

State of Kansas County, Sedgwick, ss.

Hal C. Porter (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Hal C. Porter

(Address) 900 N Tyler Rd #14, Wichita KS 67212



Subscribed and SWORN TO before me this 11th day of April, 2005. Julie Burrows Notary Public My Commission Expires: March 10, 2009

Bh

X

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25072-00-00  
Spot: W2W25W Sec/Twnshp/Rge: 17-11S-20W  
1305 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: ROSEMARY Well Number: 17-1X  
County: ELLIS Total Vertical Depth: 3800 feet

Operator License No.: 32511  
Op Name: IMPERIAL AMERICAN OIL CORPORATI  
Address: 303 N. CARROLL BLVD. #214  
DENTON, TX 76201

Production Casing Size: 5.5 feet: 3795 w/150 sxs cmt  
Surface Casing Size: 8.625 feet: 238 w/160 sxs cmt

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/27/2003 12:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: MIKE STANTON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-4459

Proposed Plugging Method: Ordered 200 sxs cement and 500# hulls.  
Perfs at 1250' - 1254'; 666' - 670'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/27/2003 3:00 PM

KCC Agent: ROGER MOSES

**Actual Plugging Report:**

8 5/8" S.P. at 238' w/160 sxs cement, 5 1/2" casing at 3795' w/150 sxs cement.  
Port collar at 1550' w/200 sxs cement.  
Ran tubing to 1552' - circulated with 120 sxs cement and 300# hulls.  
Pulled tubing - squeezed 5 1/2" with 10 sxs cement and 200# hulls.  
Max. P.S.I. 900#. S.I.P. 500#.  
Visual inspection of annulus - full.  
Total of 130 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED  
APR 12 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger L Moses  
(TECHNICIAN)

10V 03 2003

**ALLIED CEMENTING CO., INC.**

P.O. BOX 31  
 RUSSELL, KS 67665  
 PH (785) 483-3887  
 FAX (785) 483-5566  
 FEDERAL TAX ID# 48-0727860

\*\*\*\*\*  
 \* INVOICE \*  
 \*\*\*\*\*

Invoice Number: 091437

Invoice Date: 10/30/03

Sold Imperial American Oil Cor  
 To: 303 N. Carroll Blvd.,  
 #214  
 Denton, TX  
 76201

Cust I.D.....: ImpAm  
 P.O. Number...: Rosemary 17-1X  
 P.O. Date....: 10/30/03

Due Date.: 11/29/03  
 Terms....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	78.00	SKS	7.1500	557.70	T
Pozmix	52.00	SKS	3.8000	197.60	T
Gel	9.00	SKS	10.0000	90.00	T
Hulls	5.00	SKS	18.0000	90.00	T
Handling	175.00	SKS	1.1500	201.25	T
Mileage (40)	40.00	MILE	8.7500	350.00	T
175 sks @\$ .05 per sk per mi					
Plug	1.00	JOB	475.0000	475.00	T
Mileage pmp trk	40.00	MILE	3.5000	140.00	T

All Prices Are Net, Payable 30 Days Following  
 Date of Invoice. 1 1/2% Charged Thereafter.  
 If Account CURRENT take Discount of \$210.15  
 ONLY if paid within 30 days from Invoice Date

Subtotal:	2101.55
Tax.....:	142.90
Payments:	0.00
Total....:	2244.45

*Rosemary Kitchman W.O.*  
*P&A*

9090  
 Cement to Plug Well

2101.55  
203430

RECEIVED  
 APR 12 2005  
 KCC WICHITA

