

15-065-03250-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Tedro

WELL NUMBER #1

SPOT LOCATION NE NW NW

SEC. 30 TWP. 6 RGE. 25 (E) of (W)

COUNTY Graham

Date Well Completed 11-25-5

Plugging Commenced 4-22-86

Plugging Completed 4-30-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, Ks. 67665

PHONE # 013-483-5243 OPERATORS LICENSE NO. 5135

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six (6)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3880'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	300'	None
				5-1/2"	3879'	897.89'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3700' and 5 sacks cement. Shot casing at 1800', 1600', 1400', 1200' and 900'. Pulled 29 joints of 5-1/2" casing. Halliburton squeezed well with 4 sacks hulls, 23 sacks gel, 100 sacks cement blended with 1 sack hulls, 17 sack gel and 80 sacks 60/40 pozmix cement with 6% added gel and 3% calcium chloride Maximum pressure was 300 psi and shutin 150 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

STATE CORPORATION COMMISSION
MAY 09 1986
5-9-86
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1986

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton, County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

My Commission expires: