



15-065-20399-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

DEC 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

12-16-70

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Victor Justus of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Justus guarantees payment of the plugging fee.

Operator's full Name: Magness Petroleum Company,

Complete Address: 300 Nat'l Foundation Life Bldg., Oklahoma City, Okla.

Lease Name: Jeffrey Well No. 1

Location: NE-NE-SW Sec. 32 Twp. 6 Rge. (E)(W) 25

County: Graham Total Depth 3890' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Justus was instructed to plug the well as follows:

310'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1050.

Circulate hole with heavy mud. Pull DP to 1275' and displace 100 Sx.  
cement thru DP. Pull DP to 340' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent