

State of Kansas



15-005-20116-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

JAN 2 1968
1-2-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Wayne Dobbs of E. K. Edmiston has this date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston,

Complete Address: 425 First National Bank Bldg., Wichita, Kansas.

Lease Name: Conoco-Bangle Well No. 1

Location: SW-SE-NW Sec. 8 Twp. 6 Rge. (E)(W) 25

County Graham Total Depth 3795' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

211'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota section from 1075' to 1250'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent