

State of Kansas



15-065-20100-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 26 1967  
12-26-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name: Brewster Well No. 1

Location: S/2-NW-NW Sec. 31 Twp. 6 Rge. (E)(W) 25

County Graham Total Depth 3900 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

32 1/2" -- 8 5/8" Surface pipe, cement circulated with 225 Sx.  
Dakota section from 1075' to 885'. Landowner requests well be left open  
in surface casing for potential fresh water well.

Circulate hole with heavy mud. Pull DP to 1100' and displace 100 Sx.  
cement thru DP. Pull DP to 360' and displace 20 Sx. cement thru DP.  
Leave top of hole unplugged for landowner.

Very truly yours,

M. L. Nichols  
Conservation Division Agent