

State of Kansas



15-065-20037-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 1967
58-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name: Ward Well No. 2

Location: NW-NE-SW Sec. 31 Twp. 6 Rge. (E)(W)25

County Graham Total Depth 2407 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

299'--8 5/8" Surface pipe, cement circulated with 200 Sx. Lost circulation was encountered on top of Anhydrite. After cementing hole six times without regaining circulation it was decided to drill hole dry to base of Anhydrite & log.

Set bridge @ 350' with 1 sack hulls and plug with 25 Sx. cement.
Set bridge @ 295' with 1/2 sack hulls and plug with 15 Sx. cement.
Fill hole with heavy mud to 40', set plug with 1/2 sk. hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent