

State of Kansas



15-065-19038-00-00

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 17 1964  
2-17-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Inc., has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita, Russell, Kansas.

Lease Name: Ward Well No. 1

Location: NE-SW-SE Sec. 31 Twp. 6 Rge. (E) (W) 25

County Graham Total Depth 3895 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

- 265'--8 5/8" Surface pipe, cement circulated with 150 Sx.
- Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.
- " " 250 with 1/4 Sk. hulls & 20 Sx. cement.
- " " 40 with 1/2 Sk. hulls & 10 Sx. cement.

Very truly yours,

*W. L. Nichols*