



15-179-30082-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas

12-8-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Mowry Well No. 1

Location: NW-NW-SW Sec. 22 Twp. 6 Rge. (E)(W) 26

County: Sheridan Total Depth Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

359'--7" OD Surface casing, cement circulated with 160 Sx. (6 1/4" Hole).
3939'--4 1/2" Production casing cemented on bottom with 125 Sx. Top perforations from 3754' to 3751'. Well plugged back to 3906'.

Push plug to 3700', sand back to 3650' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 105 Sx. cement staged.

Very truly yours,

K. L. Nichols
Conservation Division Agent