



15-179-30080-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1970
CONSERVATION DIVISION
Wichita, Kansas 11-12-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob White of Empire Drilling Company has this date requested permission to plug the following described well:

Mr. White guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Brewster Well No. 1

Location: SW-SW-^{NW}SW Sec. 22 Twp. 6 Rge. (E)(W) 26

County: Sheridan Total Depth 3942' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. White was instructed to plug the well as follows:

299'--8 5/8" Surface casing, cement circulated with 175 Sx.
3940'--5 1/2" Production casing cemented on bottom with 125 Sx. Top perforations from 3760' to 3766'.

Sand well back to 3750' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 135 Sx. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent