

State of Kansas



15-179-20003-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1967
2-13-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Co., has this
date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Babk Bldg. Wichita, Kansas.

Lease Name: Brewster Well No. 2

Location: Cn/2-SW-NW Sec. 22 Twp. 6 Rge. (E)(W) 26

County Sheridan Total Depth 3955 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

303'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

" " 300' with 1/4 sk. hulls & 25 Sx. cement.
" " 30' with 1/4 sk. hulls & 5 Sx. cement

Very truly yours,

W. L. Nichols
Conservation Division Agent