

State of Kansas



15-179-20380-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1974
CONSERVATION DIVISION
Wichita, Kansas
3-26-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delaney of R & W Drlg. has this
date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co.

Complete Address: 435 Page Court 220 W. Douglas, Wichita Ks.

Lease Name: Brandt Well No. 1

Location: 120' W of SE SE SE Sec. 27 Twp. 6 Rge. (E)(W) 26

County: Sheridan Total Depth 4025' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Delaney was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1200' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Messing
Conservation Division Agent