



15-179-20287-06-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1971
CONSERVATION DIVISION
Wichita, Kansas
7-16-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Flake of Woodman-Tannitti Drlg. Co., has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Wente Well No. A-1

Location: SW-SW-SE Sec. 26 Twp. 6 Rge. (E)(W) 26

County: Sheridan Total Depth 4010' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

357'--8 5/8" Surface casing, cement circulated with 230 Sx.
Top of Dakota section @ 1075'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx.
cement thru DP. Pull DP to 375' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent