



15-179-20245-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1970

CONSERVATION DIVISION
Wichita, Kansas

3-30-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert & Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Nadel-Gussman,

Complete Address: 1714 First National Bldg., Tulsa, Oklahoma.

Lease Name: Brandt Well No. 1

Location: SW-SW Sec. 26 Twp. 6 Rge. (E)(W) 26

County: Sheridan Total Depth 4032 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

308'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1150'.

Circulate hole with heavy mud. Pull DP to 1375' and displace 100 Sx.
cement thru DP. Pull DP to 335' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent