

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-179-20036-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
MAY 26 1967
CONSERVATION DIVISION
Wichita, Kansas
11-17-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Marx Well No. 1

Location: NW-SW-SE Sec. 24 Twp. 6 Rge. (E)(W) 26

County Sheridan Total Depth 3939 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

318'--7" OD Surface pipe, cement circulated with 115 Sx.
3938'--4 1/2" Production casing cemented on bottom with 100 Sx. Well
plugged back to 3906'. Top perforations from 3832' to 3835'.

Sand well back to 3820' and set 3 Sx. cement with dump bailer. Pull
4 1/2" casing and squeeze well with 17 sacks gel plus 5 sacks hulls in in-
itial gel and 85 Sx. cement.

Very truly yours,

Conservation Division Agent