



15-179-19000-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED
APR 13 1971
CONSERVATION DIVISION
Wichita, Kansas

4-13-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. George Sowles of A. L. Abercrombie, Inc., has this

date requested permission to plug the following described well:

Mr. Sowles guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Vahling Well No. 2

Location: SW-NW-SW Sec. 24 Twp. 6 Rge. (E)(W) 26

County: Sheridan Total Depth 4114' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sowles was instructed to plug the well as follows:

341'--8 5/8" Surface casing cement circulated with 260 Sx. (6 3/4" Mole).
4095'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged
back to 4082'. Top perforations @ 3857'.

Push plug to 3800', sand well back to 3775' and set 3 Sx. cement with dump
bailer. Pull 4 1/2" casing and squeeze well with 4 sacks hulls, 30 sacks gel
and 160 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent