



15-179-05308-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1971
CONSERVATION DIVISION
Wichita, Kansas
4-12-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. George Sowles of A. L. Abercrombie, Inc., has this date requested permission to plug the following described well:

Mr. Sowles guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Vahling Well No. 1

Location: SW-NE-SW Sec. 24 Twp. 6 Rge. (E)(W) 26

County: Sheridan Total Depth 4258' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sowles was instructed to plug the well as follows:

349'--8 5/8" Surface casing cement circulated (6 3/4" Hole).
4100'--4 1/2" casing cemented on bottom with 125 Sx. Well plugged back to
4063'. Top perforations @ 3760'.

Push plug to 3700', sand back to 3675' and set 3 Sx. cement with dump
baller. Pull 4 1/2" casing and squeeze well with 4 sacks gulls, 30 sacks
gel and 160 Cu. Ft. cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent