

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20143-00-00

RECEIVED
10-2-68
STATE CORPORATION COMMISSION
OCT 2 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dunne-Gardner Petroleum, Incorporated,

Complete Address: 300 Schweiter Building, Wichita, Kansas.

Lease Name Banta Well No. 1

Location SW-NW-NE Sec. 9 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 3900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Dunne-Gardner Drilling Company, Incorporated,

Address: 300 Schweiter Building, Wichita, Kansas. License No.

Operation Completed: Hour 5:00 PM Day 30 Month 9 Year 1968

The Above well was plugged as follows:

2 1/4'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1220' and displaced 100 Sx. cement thru
DP from 1220' to 895'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 195'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. S. Nichols*
Well Plugging Supervisor

DATE 10/2/68
INV. NO. 8561-W