

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

JAN 2 1968

1-2-68

15-179-20066-00-00

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Slipke Well No. 1

Location CNE-NE Sec. 1 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 4110'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor Above

Address          License No.         

Operation Completed: Hour 4:00 PM Day 30 Month 12 Year 1967

The above well was plugged as follows:

224'--8 5/8" Surface pipe, cement circulated with 170 Sx.  
Dakota section from 1050' to 1225'.

Circulated hole with heavy mud. Pulled DP <sup>to 930'</sup> and displaced 100 Sx. cement thru DP from  
1250' to 930'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240' to  
180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 1-3-68

INV. NO. 7030-W