

KANSAS

JL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-30082-0000

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas
12-8-70

Operator's Full Name Okmar Oil Company,
Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.
Lease Name Mowry Well No. 1
Location NW-NW-SW Sec. 22 Twp. 6 Rge. (E) (W) 26
County Sheridan Total Depth 3940'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 2:15 PM Day 1 Month 12 Year 1970

The above well was plugged as follows:

359'--7" OD Surface casing, cement circulated with 160 Sx. (6 1/4" Hole).
3939'--4 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3906'. Top perforations from 3754' to 3751'.
Pushed plug to 3700', sanded back to 3650' and set 3 Sx. cement with dump bailer.
Pulled 4 1/2" casing (1330') and squeezed well initially with 5 sacks hulls and 8 sacks gel then 75 Sx. cement from 1300' to 975' then 12 sacks gel from 975' to 375' and followed with 20 Sx. cement from 375' to 275' then 5 sacks gel from 275' to 50' and finally 10 Sx. cement from 50' to bottom of cellar. Maximum pump-in pressure-275#.
Final shut-in pressure-200#.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 12/8/70
INV. NO. 3015-4