

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-30080-00-00

RECEIVED
THE CORPORATION COMMISSION
NOV 12 1970
CONSERVATION DIVISION
Wichita, Kansas
11-12-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Brewster Well No. 1

Location SW-SW-^{NW}SW Sec. 22 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 3942'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor David Litan Cable Tools,

Address Box #1137, Wichita, Kansas. License No.

Operation Completed: Hour 2:00 PM Day 9 Month 11 Year 1970

The above well was plugged as follows:

299'--8 5/8" Surface casing, cement circulated with 175 Sx.
3940'--5 1/2" Production casing cemented on bottom with 125 Sx. Top of cement @ 3468'.
(Temperature Survey). Top perforations from 3760' to 3766'.

Sanded well back to 3750' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed with 100
Sx. cement from 1350' to 1025'. Then 18 sacks gel from 1025' to 325' and followed
with 25 Sx. cement from 325' to 250' then 5 sacks gel from 250' to 40' and finally 10
Sx. cement from 40' to bottom of cellar. (Mudding and cementing by Halliburton).

Maximum pump-in pressure-350#. Final shut-in pressure-200#. (Recovered 1148' 5 1/2" Csg).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 11/12/70

INV. NO. 2837-W