

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20003-00-00

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1967

2-13-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Brewster Well No. 2

Location C-N/2-SW-NW Sec. 22 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 3955

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 9:00AM Day 7 Month 2 Year 1967

The Above well was plugged as follows:

303'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 300', set plug with 1/4 sack hulls and dis-

placed 25 Sx. cement thru DP. Heavy mud to 30', set plug with 1/2 sack

hulls and 5 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. A. Nichols
Well Plugging Supervisor

DATE 2/13/67
INV. NO. 4953-U