

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20370-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1973
CONSERVATION DIVISION
Wichita, Kansas
12-10-73

Operator's Full Name Tomlinson Oil Company, Incorporated,

Complete Address Suite 1030, 200 West Douglas, Wichita, Kansas.

Lease Name Wente Well No. 1

Location NE-NW-SW Sec. 36 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 3946'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address 905 Century Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 4:00 PM Day 5 Month 12 Year 1973

The above well was plugged as follows:

274'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 110 Cu. Ft. cement
thru DP from 1325' to 1000'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 12/10/73

INV. NO. 8269-W

Signed: A. L. Deibel
Well Plugging Supervisor