

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-30083-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JAN 12 1967

1-12-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Halliburton Oil Producing Company,

Complete Address: 520 Cameron Building, Oklahoma City, Oklahoma.

Lease Name Slipke Well No. 1

Location NE-NE-SE Sec. 21 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 3935

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Empire Drilling Company,

Address: 650 4th National Bank Bldg., Wichita, Kans. License No. \_\_\_\_\_

Operation Completed: Hour 1:30PM Day 5 Month 1 Year 1967

The Above well was plugged as follows:

354'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 360', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sk.

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 1/12/67  
INV. NO. 4596-11

Signed: M. L. Nichols  
Well Plugging Supervisor