

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1967

6-29-67

CONSERVATION DIVISION
Wichita, Kansas

15-179-20018-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Halliburton Oil Producing Company,
 Complete Address: 520 Cameron Building, Oklahoma City, Oklahoma. 73106
 Lease Name Wente Well No. 2
 Location NW-SE-NE Sec. 21 Twp. 6 Rge. (E) (W) 26
 County Sheridan Total Depth 3920'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated:
 Plugging Contractor: Paine Drilling Company, Incorporated,
 Address: Box "D", Hill City, Kansas. License No.
 Operation Completed: Hour 12:00M Day 27 Month 6 Year 1967

The Above well was plugged as follows:

347'--7" OD Surface pipe, cement circulated with 150 Sx. (6 1/4" hole).
Circulated hole with heavy mud, set plug @ 600' and displaced 25 Sx.
cement thru DP. Heavy mud to 360', set plug with 1/2 sack hulls and dis-
placed 15 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:

M. L. T. Jochel

Well Plugging Supervisor

DATE 6/29/67
INV. NO. 5491-W