

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20368-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1973

CONSERVATION DIVISION
Wichita, Kansas

10-23-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Brandt Well No. D-1

Location NW-SE-SW Sec. 26 Twp. 6 Rge. (E) (W)26

County Sheridan Total Depth 4020'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 5:15 PM Day 15 Month 10 Year 1973

The above well was plugged as follows:

367'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 110 Cu. Ft. cement
thru DP from 1375' to 1050'. Pulled DP to 375' and displaced 30 Cu. Ft. cement thru
DP from 375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 10/23/73

INV. NO. 8040-W

Signed: W. L. Drelak
Well Plugging Supervisor