

KANSAS

M

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20281-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1971
CONSERVATION DIVISION
Wichita, Kansas

7-16-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Wentzen Well No. A-1

Location SW-SW-SE Sec. 26 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 4010'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Woodman-Tannitti Drilling Company,

Address 706 Union National Bank Building, Wichita, Ks. License No.

Operation Completed: Hour 6:30 PM Day 13 Month 7 Year 1971

The above well was plugged as follows:

357'--8 5/8" Surface casing, cement circulated with 230 Sx.
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru
DP from 1300' to 975'. Pulled DP to 375' and displaced 25 Sx. cement thru DP from
375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickel
Well Plugging Supervisor

INVOICED

DATE 7/16/71
INV. NO. 4009-W