

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20245-00-00

RECEIVED 3-30-70
STATE CORPORATION COMMISSION
MAR 30 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Nadel & Gussman,

Complete Address 1714 First National Building, Tulsa, Oklahoma.

Lease Name Brandt Well No. 1

Location SW-SW Sec. 26 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 4032'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert & Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 6:30 PM Day 23 Month 3 Year 1970

The above well was plugged as follows:

308'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 100 Sx. cement thru
DP from 1375' to 1050'. Pulled DP to 335' and displaced 25 Sx. cement thru DP from
335' to 260'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 3-30-70
INV. NO. 1652-W