

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20285-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
7-13-71

Operator's Full Name Okmar Oil Company.  
Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.  
Lease Name Dempewolf Well No. 1  
Location SE-SW Sec. 25 Twp. 6 Rge. (E) (W) 26  
County Sheridan Total Depth 3970'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Woodman-Tannitti Drilling Company,  
Address 706 Union antional Building, Wichita, Kansas. License No.         
Operation Completed: Hour 4:00 AM Day 6 Month 7 Year 1971

The above well was plugged as follows:

357'-p8 5/8" Surface casing, cement circulated with 230 Sx.  
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru  
DP from 1300' to 975'. Pulled DP to 370' and displaced 25 Sx. cement thru DP from  
370' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 7/14/71  
INV. NO. 3982-W