

KANSAS

Form CP-3
Rev. 6-26-62

B

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20166-0000

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1968
CONSERVATION DIVISION
Wichita, Kansas

12-24-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tilco Et al.

Complete Address: 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name Horton Well No. 1

Location SW-SW-NW Sec. 34 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 4065'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated.

Address: Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 2:00 PM Day 18 Month 12 Year 1968

The Above well was plugged as follows:

322'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 100 Sx. cement thru
DP from 1375' to 1050'. Pulled DP to 335' and displaced 20 Sx. cement thru DP from
335' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 12-24-68

INV. NO. 9091-W