

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-179-20380-00-00

Rec'd  
3-29-74

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address 435 Page Ct. 220 W. Douglas Wichita, Kansas

Lease Name Brandt Well No. 1

Location 120' W of SE SE SE Sec. 27 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 4025'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 3:30 P Day 23 Month 3 Year 1974

The above well was plugged as follows:

RTD 4025' 8 5/8 csg set at 368' cwc Cmt. Mat. 50-50 poz W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 1200' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 3/28/74  
INV. NO. 8824-W

Signed: Leo F. Massey  
Well Plugging Supervisor