

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22677-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 32-6S-23W
330 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: WALTERS Well Number: 1
County: GRAHAM Total Vertical Depth: 3974 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: \$129.16
Surface Casing: Size 8.625 feet: 303 190 SX CMT
Production: Size 5.5 feet: 3972 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/27/2002 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 15 sxs gel - 500# hulls.
Port collar at 2168' cwc.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 09/27/2002 11:15 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. Cementer to 5 1/2" casing.
Squeezed 30 sxs 60/40 pozmix - 10% gel with 600# hulls, followed with 15 sxs gel, followed with 170 sxs cement.
Max. P.S.I. 1000#. S.I.P. 1000#.
Pressured-up 8 5/8" casing to 500#.

RECEIVED
OCT 17 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 10-18-02

INV. NO. 2003060656

OCT 16 2002

STATE: KANSAS COUNTY: GRAHAM REISSUE 32-6S-23W
FIELD: WHITE SW SW SW
OPER: RITCHIE EXPL 330 FSL 4950 FEL SEC
WELL: 1 WALTERS M WELL CLASS: DO ELEV: 2502 KB
API: 15-065-22677 STATUS: OIL 2497 GR
SPUD: 05/13/92 COMP: 06/16/92
DTD: 3974 LTD: 3973 FTD: PENNSYLVANIAN PBD: 3962

LOC: 8 1/4 MI N/NW HILL CITY, KS

IP: COMP 6/16/92, IPP 20 BO, 37 BWPD PROD ZONE- LANSING-KANSAS CITY
3789-3806(GROSS)
NO CORES, THREE DSTS

LOG TOPS:

STONE CORRAL	2183 319	TORONTO	3744 -1242
B/ STONE CORRAL	2217 285	LANSING	3761 -1259
TOPEKA	3519 -1017	B/ KANSAS CITY	3951 -1449
HEEBNER	3720 -1218		
TD	3974 -1472		

LOG TYPES: GRDL;

CSGS: 8 5/8 @ 303 W/190 SX, 5 1/2 @ 3972 W/250 SX, MULTISTAGE COLLAR @ 2168

W/250 SX; TBG: 2 3/8 @ 3016; DRLG COMP 05/19/92 RIG REL 05/19/92

DSTS: DST # 1 (LANSING-KANSAS CITY) 3780-3800, OP 45 MIN, SI 45 MIN,

(OVER)

COPYRIGHT 1994 PETROLEUM INFORMATION CORPORATION

DATE 09/23/94 CARD #00053-KS