

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21154-00-00
Spot: S2SENWSW Sec/Twnshp/Rge: 20-8S-19W
1320 feet from S Section Line, 990 feet from W Section Line
Lease Name: LOWRY Well #: 3
County: ROOKS Total Vertical Depth: 3435 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 5893 SADDLE CREEK TRAIL
PARKER, CO 80134

PROD Size: 4.5 feet: 3431 150 SX CMT
SURF Size: 8.625 feet: 286 160 SX CMT

A 111 64

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2005 8:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BRIAN KARLIN Company: SHELBY RESOURCES LLC Phone: (785) 623-3290

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Old squeeze jobs: 1984 - 935' w/150 sxs; 1989 - 934' w/125 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2005 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2175'. Allied pumped 120 sxs 60/40 pozmix - 10% gel with 400# hulls - cement circulated.
PTOH. Allied squeezed with 100 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked up to backside. Pumped 5 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3217 | 3222 | | |

RECEIVED
APR 19 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

10

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

4-19-05

APR 18 2005

NOV. 13 2005

2005061430


REPLACEMENT CARD

EAGLE PETROLEUM CORPORATION
 520 S. HOLLAND, #501
 WICHITA, KS. 67209
 CONTR ASPEN EXPLORATION

#3 LOWRY
 CITY ROOKS
 FIELD BRAY

20-8-19W
 100'S.
 C SE NW SW

ELV 1989 KB SPD 11/11/80 CARD ISSUED 9/10/81 # P 10 BOPD, NW
 LKC 3215-3226



API 15-163-21,154

| LOG | Top | Depth/Datum |
|------|-------|-------------|
| ANH | | 1462+ 527 |
| TOP | | 2937- 948 |
| HEEB | | 3141-1152 |
| LANS | | 3178-1189 |
| BKC | | 3388-1399 |
| CONG | | 3401-1412 |
| ARB | | 3428-1439 |
| RTD | | 3435-1446 |

8 5/8 " 286, 4 1/2 " 3431
 NO CORES
 DST (1) 3210-3250 (LKC) / 45-45-45-45, REC 60' MDY OIL, 300'
 CLEAN GSY OIL, 240' GCMW, SIP 803-803#, FP 65-196 / 294-
 305#
 MICT - CO, PF (LKC) 3215-3226, AC 1000 GAL, SO, POP, P 10
 BOPD, NW

CORRECTION & INFO RELEASED: 9/18/86 - ORIGINALLY FIRST
 REPORTED IN SW NW SW, ADDED WELL INFO
NOTE: INFO RELEASED: 1/7/82 - WAS OIL WELL - TIGHT HOLE.
CORRECTION: 11/4/82 - ORIGINALLY FIRST REPORTED AS SE NW
 SW, WAS MONTGOMERY DRILLING COMPANY AS CONTR

1006