

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03630-00-00
Spot: NESWNE Sec/Twnshp/Rge: 20-9S-16W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DORRA Well #: 4 704
County: ROOKS Total Vertical Depth: 3430 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3430 175 SX CMT
SURF Size: 8.625 feet: 240 175 SX CMT

111 48

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2005 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-5100

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2005 2:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

D.V. Tool at 1270' w/400 sxs cement.
Hit bridge at 550' - pushed on thru to 2000' with tubing.
Spotted 100 sxs cement with 300# hulls.
Pulled tubing to 1000' - circulated with 100 sxs cement and 500# hulls.
Pulled all tubing - squeezed with 150 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Tied to 8 5/8" x 5 1/2" annulus. Pressured to Max. P.S.I. 350#. Took no cement.
Total of 350 sxs 60/40 pozmix - 10% gel and 800# hulls.
Dakota 495' - 795'. Anhydrite 1270' - 1305'.

Perfs:

Top	Bot	Thru	Comments
3142	3406		

RECEIVED
APR 19 2005
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS DORR UNIT 704. ALLIED CEMENTING COMPANY. STEWART TANK-WATER.

Plugged through: TBG

District: 04

110c

Signed Roger L. Moses
(TECHNICIAN)

INVOICED

DATE 4-19-05

INV. NO. 2005061429

APR 18 2005

WARRANTY

CITIES SERVICE #1 DORR 'A' 20-9-16W
 Contr. **BRADEN DRILLING COMPANY** **ROOKS** County **NE SW NE**
 E 2025 Comm. 7-14-56 Comp. 8-10-56 IP 103 BOFD

Tops	Depth	Datum
Anh	1270-1305	
TOP	2903	- 878
HEEB	3124	-1099
DOD	3142	-1117
LANS	3166	-1141
B/KC	3415	-1390
TD	3430	-1405

Casing
 8" 240
 5" 3430
 DST 3250-77/1 HR, 36' M & WTR,
 BHP 435#
 PERF 322/1242-3406: ACID 6500,
 PMP 103 BO & 77 BW

Dorr Pool

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS