

6-090482

4-2

107
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,671-0000
SE NW SE /4 SEC. 14, 06 S, 23 W
1650 feet from S section line
1650 feet from E section line

Operator license# 4767 Lease Beckman Well # 1

Operator: Ritchie Exploration, Inc. County Graham

Address: 125 N. Market, Suite 1000 Well total depth 3840 feet
Wichita, Kansas 67202 Conductor Pipe: inch @ feet
(316)267-4375 Surface pipe 8 5/8 Inch @ 261 feet

124.80

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas

Company to plug at: Hour: PM Day: 31 Month: March Year: 1992

Plugging proposal received from: Lloyd Dellett

Company: Murfin Drilling Company phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2060 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1210 feet " 100 " Mousehole: 10 sacks

3rd plug @ 310 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sks.

5th plug @ feet "

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:30 AM, Day: 02, Month: April, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2360 GL, Anhydrite depth: 2040 - 2073 feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place:

Plugged through drill pipe: YES

Did Not penetrate Arbuckle, cemented by Allied Cementing Company

I did[] / did not[X] observe the plugging.

Ed Schumacher

Ed Schumacher
(agent)

Form CP-2/3

INVOICED
DATE 4-28-92
SER. NO. 34048

ED