

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,742-0000

SW NE SW /4 SEC. 34, 06 S, 23 W  
1650 feet from S section line  
3630 feet from E section line

Operator license# 4767 Lease P.E. Brassfield well # 1  
Operator: Ritchie Exploration, Inc. County Graham  
Address: 125 N. Market Well total depth 3950 feet <sup>128,37</sup>  
Suite #1000 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 1 Month: July Year: 94

Plugging proposal received from: Keith

Company: Murfin Drilling Company, Inc. Phone:           

Were: Order 190 sxs. 60/40 pozmix - 6% gel - 3% c.c.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 9:00A.M., Day: 1, Month: July, Year: 94

Actual plugging report: Spot cement plugs with drill pipe.  
1st. plug at 2100' w/25 sxs.  
2nd. plug at 1275' w/100 sxs.  
3rd. plug at 300' w/40 sxs.  
4th. plug at 40' w/10 sxs. W.P.  
Circulate 15 sxs. in rathole.

Remarks: Anhy. 2080' - 2144'.  
Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING     . Elevation: 2424

I did INVOICED [      ] observe the plugging.

Carl Goodrow 10-7-94

(agent)  
Form CP-2/3

DATE OCT 10 1994  
INV. NO. 41364

RECEIVED  
STATE CORPORATION COMMISSION

OCT 07 1994

CONSERVATION DIVISION  
WICHITA, KANSAS