

6-100455

7-21

177
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,681 ⁰⁰⁰⁰

SE NW NE /4 SEC. 23, 06 S, 24 W
4290 feet from S section line
1650 feet from E section line

Operator license# 4767

Lease G.C.L. well # 1

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 North Market, # 1000
Wichita, Kansas 67202

Well total depth 3895 feet ^{126.58}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 265 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling License# 30606

Address: Wichita, Kansas

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Lloyd Delette

Company: Murfin Drilling phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2120 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 1250 feet " 100 " Mousehole: sacks
3rd plug @ 310 feet " 40 "
4th plug @ 40 feet " Wiper plug & 10 sx.

5th plug @ feet "

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:30 am, Day: 21, Month: July, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2400 GL, Anhydrite depth: 2116 - 2148 feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: YES
Plugged through drill pipe: YES
Did NOT penetrate Arbuckle, cemented by Allied Cementing.

9-28-92
Rec'd

I did observe the plugging.

David K. Wann
David K. Wann P.I.R.T. II
(agent)

INVOICED
DATE 10-8-92
INV. NO. 36380